


UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Form approved.
Budget Bureau No. 1004-0136
Expires December 31, 1991



APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK

DRILL ☒ DEEPEN ☐

b. TYPE OF WELL

OIL WELL ☐ GAS-WELL ☒ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐

2. NAME OF OPERATOR
CHEVRON USA PRODUCTION CO., INC.

3. ADDRESS AND TELEPHONE NO.
11002 EAST, 17500 SOUTH, VERNAL, UT 84078-8526 (801) 781-4300

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface
1175' FSL, 1388' FWL, SESW
At proposed prod. zone
SAME

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
31.8 MILES FROM VERNAL, UT

15. DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any) 1175'

16. NO. OF ACRES IN LEASE
2560

17. NO. OF ACRES ASSIGNED
TO THIS WELL
NA

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT. 3493'

19. PROPOSED DEPTH
5327'

20. ROTARY OR CABLE TOOLS
ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5555' GL

22. APPROX. DATE WORK WILL START*
2/1/95

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55	24#	360'	190 SX.
7-7/8"	5-1/2" K-55	15.5#	5327'	611 SX.

We propose to drill for natural gas in the Green River Formation at the location specified. Enclosures:

- Certified Plat
- Self Certification Statement
- Thirteen Point Surface Use Plan With Attachments
- Eight Point Drilling Plan With Attachments

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED LD Conley TITLE TEAM LEADER DATE 12-19-94
(This space for Federal or State office use)

PERMIT NO. 43-047-32626 APPROVAL DATE 2/22/95

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY Matthews TITLE Petroleum Engr DATE: 2/22/95
BY: Matthews

*See Instructions On Reverse Side

WELL SPACING: BL49-2-3


T7S, R24E, S.L.B.&M.

CHEVRON U.S.A., INC.

Well location, RED WASH UNIT #314, located as shown in the SE 1/4 SW 1/4 of Section 29, T7S, R24E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT THE SOUTHWEST CORNER OF SECTION 29, T7S, R24E, S.L.B.&M. TAKEN FROM THE DINOSAUR NW, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5505 FEET.




LEGEND:

└ = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED. (Brass Caps)



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert L. Kay
REGISTERED LAND SURVEYOR
REGISTRATION NO. 184819
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85' SOUTH 200 EAST - VERNAL, UTAH 84078
(801) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 9-23-94	DATE DRAWN: 10-20-94
PARTY B.B. D.G. D.J.S.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE CHEVRON U.S.A., INC.	

CHEVRON USA PRODUCTION CO.

**RED WASH UNIT #314
1175' FSL & 1388' FWL
SESW-S29-T7S-R24E, SLB&M
UINTAH COUNTY, UTAH**

EIGHT POINT DRILLING PLAN

1. ESTIMATED FORMATION TOPS:

Uinta
Green River

Surface
~2401' to 5327' TD

**2. ESTIMATED DEPTHS OF TOP AND BOTTOM OF WATER, OIL, GAS, OR
OTHER MINERAL BEARING FORMATIONS AND PLAN FOR PROTECTION:**

Deepest Fresh Water: ~2401', top of Green River Formation. The Green River Formation is classified as an exempt aquifer in the vicinity of the proposed well.

Oil Shale: Oil shale is expected between the depths of ~3273-3353'.

Oil: None expected.

Gas: Possible gas in the Uinta Fm. below ~2100'. Expected in the Green River Fm. from ~3877' to 5177'.

Protection of oil, gas, water, or other mineral bearing formations:
Protection shall be accomplished by cementing surface casing and production casing back to the surface or to depths sufficient to isolate required formations. Please refer to casing and cement information for protection plans.

3. PRESSURE CONTROL EQUIPMENT:

For drilling surface hole to 360': No BOP equipment required.

For drilling through 8.625" surface casing to TD:

Maximum anticipated surface pressure is <1400 psi.

Pressure control equipment shall be in accordance with BLM minimum standards for 2000 psi equipment.

RED WASH UNIT #314 - EIGHT POINT DRILLING PLAN

A casing head with an 11", 3000 psi flange will be screwed or welded onto the 8.625" surface casing.

BOP stack will consist of a double gate and annular preventer. The double gate will be equipped with pipe rams on bottom and blind rams on top. The choke and kill lines will be connected to outlets between the bottom and top rams, utilizing either the ram body outlet or a drilling spool with side outlets. The BOP stack will be 9" or 11" bore, 2000 or 3000 psi working pressure. The choke and kill lines will be 2" or 3" bore, 2000 or 3000 psi working pressure. Please refer to attached schematics.

A rotating head may be used while drilling below surface casing for control of gas cut mud.

Test procedure and frequency shall be in accordance with BLM minimum standards for 2000 psi equipment.

4. SUPPLEMENTAL DRILLING EQUIPMENT AND CASING INFORMATION:

Casing Information:

Casing	Conn.	New/ Used	Stage Tool	Centralizers
8.625"	STC	New	No	10' above shoe, on 1st and 3rd collars.
5.500"	STC	New	No	10' above shoe, every other collar to top of pay ($\pm 3850'$),

Cement Information:

Casing	Cement
8.625"	Oilfield type cement circulated in. Class "A" single slurry mixed to 15.6 ppg, yield = 1.19 cf/sx. Fill to surface with 225 cf (190 sx) calculated. Tail plug used. Allowed to set under pressure.
5.500"	Lead/Tail oilfield type cement circulated in. Tail slurry: 50/50 Class H/Pozzolan + 2% gel + additives as required mixed to 14.1 ppg, yield = 1.23 cf/sx; or class G + 12.5 lb/sx gilsonite + additives as required mixed to 14.8 ppg, yield =

RED WASH UNIT #314 - EIGHT POINT DRILLING PLAN

1.34. Fill to 3550' ($\pm 300'$ above top of pay) with 407 cf (331 sx or 304 sx).

Lead slurry: Class "A" + extender + additives mixed to 11.0 ppg, yield = 3.82 cf/sx. Fill to surface with 1071 cf (280 sx).

Tail plug used. Allowed to set under pressure.

Drilling Equipment:

Surface hole will be drilled and surface casing set with small rotary surface hole rig.

A rotating head may be used while drilling below surface casing for control of gas cut mud.

5. CIRCULATING MEDIUM, MUD TYPE, MINIMUM QUANTITIES OF WEIGHT MATERIAL, AND MONITORING EQUIPMENT:

Surface hole will be drilled with air, air/mist, foam, or mud depending on hole conditions. Drilling below surface casing will be with water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash, and polymers. No chromates will be used. It is not intended to use oil in the mud, however, in the event it is used, oil concentration will be less than 4% by volume. Maximum anticipated mud weight is ± 9.5 ppg.

No minimum quantity of weight material will be required to be kept on location.

PVT/Flow Show will be used from base of surface casing to TD.

Gas detector will be used from 3500' (depth mud loggers on) to TD.

6. ANTICIPATED TYPE AND AMOUNT OF TESTING, LOGGING, AND CORING:

Logging:

Mud logging:	~3500' to TD.
Dual Induction/SP/GR:	TD-Surface casing shoe
Density/Neutron/GR with XY caliper:	TD-3500'
Sonic/GR with caliper	TD-Surface casing shoe.
MIR tool:	TD-3500'

RED WASH UNIT #314 - EIGHT POINT DRILLING PLAN

Coring:

None planned.

Testing:

Possible DST in lower Green River Fm. at wellsite geologist's discretion.

7. EXPECTED BOTTOM HOLE PRESSURE AND ANY ANTICIPATED ABNORMAL PRESSURE, TEMPERATURES, OR OTHER HAZARDS (H₂S, STEAM, ETC.) AND ASSOCIATED CONTINGENCY PLANS:

Normal pressure gradient to top of Green River Fm. Some slightly pressured (0.47 psi/ft.) gas zones within the Green River Fm. may exist, although possible pressure depleted intervals (0.37 psi/ft.) from 3877' to 5177' are viewed as greater hazards. All sands typically tight - drill underbalanced with water or unweighted mud.

Maximum expected BHP @ 5327':	~2504 psi (0.47 psi/ft.).
Maximum expected BHT @ 5327':	~135° F.

No other abnormal hazards are anticipated and no contingency plans are required.


8. OTHER:

None.

E. CLASS III BLOWOUT PREVENTER STACK:

The Class III preventer stack is designed for drilling or workover operations. It is composed of a single hydraulically operated annular preventer on top, then a blind ram preventer, a drilling spool, and a single pipe ram preventer on bottom. The choke and kill lines are installed onto the drilling spool and must have a minimum internal diameter of 2". All side outlets on the preventers or drilling spool must be flanged, studded, or clamped. An emergency kill line may be installed on the wellhead. A double ram preventer should only be used when space limitations make it necessary to remove the drilling spool. In these instances, the choke manifold should be connected to a flanged outlet between the preventer rams only. In this hookup, the pipe rams are considered master rams only, and cannot be used to routinely circulate out a kick. The Class III blowout preventer stack is shown to the right in Figure 11J.4.

Figure 11J.4
Class III Blowout Preventer Stack




CHEVRON DRILLING REFERENCE SERIES
VOLUME ELEVEN
WELL CONTROL AND BLOWOUT PREVENTION

D. CLASS III CHOKE MANIFOLD

The Class III choke manifold is suitable for Class III workovers and drilling operations. The Standard Class III choke manifold is shown in Figure 11J.8 below. Specific design features of the Class III manifold include:


1. The manifold is attached to a drilling spool or the top ram preventer side outlet.
2. The minimum internal diameter is 2" (nominal) for outlets, flanges, valves and lines.
3. Includes two steel gate valves in the choke line at the drilling spool outlet. The inside choke line valve may be remotely controlled (HCR).
4. Includes two manually adjustable chokes which are installed on both side of the manifold cross. Steel isolation gate valves are installed between both chokes and the cross, and also downstream of both chokes.
5. Includes a bleed line which runs straight through the cross and is isolated by a steel gate valve.
6. Includes a valve isolated pressure gauge suitable for drilling service which can display the casing pressure within view of the choke operator.
7. Returns through the choke manifold must be divertible through a mud-gas separator and then be routed to either the shale shaker or the reserve pit through a buffer tank or manifold arrangement.
8. If the choke manifold is remote from the wellhead, a third master valve should be installed immediately upstream of the manifold cross.



D. TYPE "B" KILL LINE — CLASS III, IV , AND V WELLS

The type B kill line described below in Figure 11J.11 is the minimum recommended hookup for installation on all Class III, Class IV and Class V wells. Specific design features of the type B kill line include:

1. The preferred kill line connection to the well is at the drilling spool, however, a preventer side outlet may be used when space restrictions exclude the use of a drilling spool. In all cases, the kill line must be installed below the uppermost blind rams so the well can be pumped into with no pipe in the hole.
2. The arrangement includes two - 2" (nominal) gate valves installed at the drilling spool and an upstream fluid cross. The outside valve may be hydraulically remote controlled.
3. Two pump-in lines should be attached to the fluid cross. The **primary kill line** should be routed to the rig standpipe where it can be manifolded to the rig pumps. The **remote kill line** should be run to a safe location away from the rig or to the rig cementing unit. The remote kill line should have a loose end connection for rigging-up a high pressure pumping unit.
4. Both the primary kill line and the remote kill line must include a 2" check valve which is in working condition while drilling. If a check valve is crippled for testing purposes, the flapper or ball must be re-installed and tested before drilling resumes.
5. The primary kill line must include a pressure gauge which can display the pump-in pressure on the rig floor.
6. Any lines which are installed at the wellhead are designated as "**emergency kill lines**" and should only be used if the primary and remote kill lines are inoperable.



United States Department of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 West
Vernal, UT 84078

SELF-CERTIFICATION STATEMENT

Be advised that Chevron USA Production Company is considered to be the operator of Red Wash Unit #314, SESW-Sec.29-T7S-R24E, Uintah County, Utah, and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for this well is provided by Nationwide Bond #U-89-75-81-34 (Standard Oil Co. of California and its wholly owned subsidiary Chevron USA Production Co., as co-principals) via surety consent as provided for in 43 CFR 3104.2.

Sincerely,



J. T. Conley
Red Wash Area Team Leader

DATE: 12-19-94

CHEVRON USA PRODUCTION CO.

**RED WASH UNIT #314
1175' FSL & 1388' FWL
SESW-S29-T7S-R24E, SLB&M
UINTAH COUNTY, UTAH**

THIRTEEN POINT SURFACE USE PLAN

1. EXISTING ROADS:

A. See Topographic Map A. There are no plans to change, alter or improve upon any existing state or county road.

B. See Topographic Map A. Travel east from Vernal on U.S. Highway 40 to the intersection with Utah State Highway 45. Turn south on Utah State 45 and proceed 20.7 miles to the Red Wash Oil and Gas Field road. Turn east and proceed 4.7 miles to existing lease road past water tank. Turn south and proceed a total of 3.5 miles on existing lease road to proposed access road.

2. ACCESS ROADS TO BE CONSTRUCTED OR RECONSTRUCTED:

See Topographic Maps A and B. The access road and location site are on Federal lands. A new access road of approximately 0.6 miles to the location will be constructed. A main drainage on the proposed access road will be diked, with the road on top of the dike. The dike will have a rip-rap spillway constructed of cut material from road construction, per onsite discussion.

3. LOCATION OF EXISTING WELLS WITHIN ONE MILE:

See Topographic Map B.

4. LOCATION OF EXISTING OR PROPOSED FACILITIES IF WELL IS PRODUCTIVE:

A. See Topographic Map C.

B. Gas dehydration and metering equipment will be installed onsite following completion of the new wellbore. No blooie pit will be constructed, as a tank will be installed in its place.

RWU #314 - THIRTEEN POINT SURFACE USE PLAN

C. A gas pipeline approximately 3200' in length will be constructed to connect the well to the existing gas gathering system. The pipeline will follow the proposed access road to the tie-in.

D. Disturbed areas no longer needed for operations will be graded back to as near original state as possible. Drainage channels will be returned to original state and the areas will be reseeded as prescribed by the BLM.

5. LOCATION AND TYPE OF WATER SUPPLY:

Red Wash Unit fresh water supply, Application #A17791, Water Right Number 49-2153. Water will be picked up at water tank shown on Topographic Map A, ~4.1 miles from wellsite on proposed access route.

Transportation of water shall be by tank truck.

6. CONSTRUCTION MATERIALS:

Native dirt and gravel will be used as construction materials.

7. METHODS FOR HANDLING WASTE DISPOSAL:

A. A closed mud system is planned, requiring a trench for the reserve tank.

B. Excess reserve pit fluid will be disposed of via haul-off to a commercial disposal facility.

C. Drill cuttings will be caught and settled in the reserve tank and buried when the trench is backfilled.

D. Commercial service will provide portable toilets and haul-off to a commercial disposal facility.

E. Trash will be stored in trash containers and hauled to commercial or municipal facility for disposal.

F. It is not anticipated that any salt or chemicals will need to be disposed of. If required, disposal will be by commercial disposal facility.

RWU #314 - THIRTEEN POINT SURFACE USE PLAN

G. In the event fluids are produced, any gas and associated condensate will be flared over the flare pit while testing. Any produced water will be caught in the flare pit and transferred to Red Wash Central Battery for use in the waterflood system. Depending on the nature of completion/stimulation fluids, these will be caught in the flare pit and disposed of via use in the waterflood system, evaporation or haul-off to a commercial disposal facility.

H. Hazardous chemicals 10,000lb. of which will most likely be used, produced, stored, transported or disposed of in association with the proposed action of drilling, completing and producing this well: We anticipate that none of the hazardous chemicals in quantities of 10,000 lb. or more will be associated with these operations.

I. Extremely hazardous substances threshold quantities of which will be used, produced, stored, transported or disposed of in association with the proposed action of drilling, completing and producing this well: We anticipate that none of the extremely hazardous substances in threshold quantities per 40 CFR 355 will be associated with these operations.

8. ANCILLARY FACILITIES:

None.

9. WELLSITE LAYOUT:

A. See Figures 1 and 2. A closed mud system is planned. In the event that a closed mud system is not available, a reserve pit will be constructed as shown. The reserve pit will be lined if required.

B. Burn pit will not be lined.

C. Access to the well pad will be as shown on Topographic Map B.

10. PLAN FOR RESTORATION OF SURFACE:

A. All surface areas not required for production operations will be graded to as near original condition as possible and contoured to maintain possible erosion to a minimum. Any rock encountered in excavation will be disposed of beneath backfill to return surface to its present appearance and provide soil for seed growth.

RWU #314 - THIRTEEN POINT SURFACE USE PLAN

B. The topsoil will be evenly distributed over the disturbed areas. Reseeding will be performed as directed by the BLM.

C. Pits that would present a hazard to wildlife or livestock will be backfilled when the rig is released and removed.

D. Completion of the well is planned during 1995. Rehabilitation will commence following completion of the well. If the wellsite is to be abandoned, all disturbed areas will be recontoured to the natural contour as soon as possible.

11. SURFACE OWNERSHIP:

The wellsite, access roads and flowlines are on Federal land. The operator shall contact the BLM office at (801) 789-1362 between 24 and 48 hours prior to construction activities.

12. OTHER INFORMATION:

A. The well is located in hilly and sandy terrain. Vegetation consists of sagebrush and natural grasses around the location. The soil is a poorly developed, semi-arid, thin topsoil layer over the Uintah Formation.

B. Surface use activities other than the oil and gas well facilities consist of grazing.

C. There are no occupied dwellings near the wellsite.

D. Archeological clearance was recommended during a 12/6/94 meeting between BLM, Chevron and Senco-Phenix personnel.

RWU #314 - THIRTEEN POINT SURFACE USE PLAN

13. COMPANY REPRESENTATIVE:

Mr. J. T. Conley
11002 East 17500 South
Vernal, UT 84078
(801) 781-4301

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Chevron USA Production Co., Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

12-19-94
Date

J. T. Conley
J. T. Conley
Red Wash Area Team Leader

CHEVRON USA., INC.


LOCATION LAYOUT FOR

RED WASH UNIT #314
SECTION 29, T7S, R24E, S.L.B.&M.

1175' FSL 1388' FWL

FIGURE #1

SCALE: 1" = 50'
DATE: 10-20-94
Drawn By: D.J.S.



Elev. Ungraded Ground at Location Stake = 5554.6'

Elev. Graded Ground at Location Stake = 5554.0'


UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (801) 789-1017

CHEVRON USA., INC.



TYPICAL CROSS SECTIONS FOR

RED WASH UNIT #314
SECTION 29, T7S, R24E, S.L.B.&M.
1175' FSL 1388' FWL

FIGURE #2



DATE: 10-20-94
Drawn By: D.J.S.



NOTE:

Topsail should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE YARDAGES

CUT

(6") Topsoil Stripping = 1,320 Cu. Yds.
Remaining Location = 10,630 Cu. Yds.

TOTAL CUT = 11,950 CU.YDS.

FILL = 8,580 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION

= 2,920 Cu. Yds.

Topsoil & Pit Backfill (1/2 Pit Vol.)


= 2,920 Cu. Yds.

EXCESS CUT MATERIAL

= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East • Vernal, Utah 84078 • (801) 789-1017




TOPOGRAPHIC
MAP "A"

DATE: 10-20-94 J.D.S.



CHEVRON U.S.A. INC.

RED WASH UNIT #314
SECTION 29, T7S, R24E, S.L.B.&M.
1175' FSL 1388' FWL




TOPOGRAPHIC
MAP "B"

SCALE: 1" = 2000'
DATE: 10-20-94 J.D.S.



CHEVRON U.S.A. INC.

RED WASH UNIT #314
SECTION 29, T7S, R24E, S.L.B.&M.
1175' FSL 1388' FWL



**TOPOGRAPHIC
MAP "C"**

LEGEND:

- EXISTING PIPELINE
- |-|-|-|- Proposed Pipeline



CHEVRON U.S.A. INC.

RED WASH UNIT #314
SECTION 29, T7S, R24E, S.L.B.&M.

DATE: 10-20-94 J.D.S.

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 12/21/94

API NO. ASSIGNED: 43-047-32626

WELL NAME: RED WASH #314
OPERATOR: CHEVRON USA PRODUCTION (N0210)

PROPOSED LOCATION:

SESW 29 - T07S - R24E
SURFACE: 1175-FSL-1388-FWL
BOTTOM: 1175-FSL-1388-FWL
UINTAH COUNTY
RED WASH FIELD (665)

LEASE TYPE: FED
LEASE NUMBER: SL-071965

PROPOSED PRODUCING FORMATION: GRRV

INSPECT LOCATION BY: / /

TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Federal ☒ State ☐ Fee ☐
(Number 44-89-75-81-34)
☒ Potash (Y/N)
☒ Oil shale (Y/N)
☒ Water permit
(Number 44-2153)
☒ RDCC Review (Y/N)
(Date: _____)

LOCATION AND SITING:

☒ R649-2-3. Unit: 44-63010x
☐ R649-3-2. General.
☐ R649-3-3. Exception.
☐ Drilling Unit.
Board Cause no: _____
Date: _____

COMMENTS: _____

STIPULATIONS: _____

RED WASH UNIT INFILL DEVELOPMENT CHEVRON
T 7 & 8 S, R 24 E UTAH COUNTY

• RED WASH 307

• RED WASH 317

• RED WASH 313*

• RED WASH 306

R 24 E

R 25 E

• RED WASH 319*

• RED WASH 314

• RED WASH 308

• RED WASH 311

• RED WASH 320

• RED WASH 315

T 7 S

R 24 E

T 8 S

• RED WASH 318

• RED WASH 309

STATE OF UTAH

Operator: CHEVRON USA PRODUCTION	Well Name: RED WASH #314
Project ID: 43-047-32626	Location: SEC. 29 - T07S - R24E

Design Parameters:

Mud weight (9.50 ppg) : 0.494 psi/ft
 Shut in surface pressure : 2318 psi
 Internal gradient (burst) : 0.058 psi/ft
 Annular gradient (burst) : 0.000 psi/ft
 Tensile load is determined using buoyed weight
 Service rating is "Sweet"

Design Factors:

Collapse : 1.125
 Burst : 1.00
 8 Round : 1.80 (J)
 Buttress : 1.60 (J)
 Other : 1.50 (J)
 Body Yield : 1.50 (B)

Length (feet)		Size (in.)	Weight (lb/ft)	Grade	Joint	Depth (feet)	Drift (in.)	Cost	
1	5,327	5.500	15.50	K-55	ST&C	5,327	4.825		
	Load (psi)	Collapse Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Tension Load (kips)	Strgth (kips)	S.F.
1	2629	4040	1.537	2629	4810	1.83	70.58	222	3.15 J

Prepared by : FRM, Salt Lake City, UT
 Date : 02-23-1995
 Remarks :

Minimum segment length for the 5,327 foot well is 1,000 feet.
 SICP is based on the ideal gas law, a gas gravity of 0.69, and a mean gas temperature of 101°F (Surface 74°F , BHT 127°F & temp. gradient 1.000°/100 ft.)
 The mud gradient and bottom hole pressures (for burst) are 0.494 psi/ft and 2,629 psi, respectively.

NOTE: The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1987 pricing model. (Version 1.06)



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

February 22, 1995

Chevron USA Production Company
11002 East 17500 South
Vernal, Utah 84078-8526


Re: Red Wash #314 Well, 1175' FSL, 1388' FWL, SE SW, Sec. 29, T. 7 S., R. 24 E.,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Admin. R. 649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-32626.

Sincerely,


for R. J. Firth
Associate Director

ldc

Enclosures

cc: Uintah County Assessor

Bureau of Land Management, Vernal District Office

WAPD

Operator: Chevron USA Production Company, Inc.

Well Name & Number: Red Wash #314

API Number: 43-047-32626

Lease: Federal SL-071965

Location: SE SW Sec. 29 T. 7 S. R. 24 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT TO PUBLIC
(Other instructions
reverse side)
MAR 1 - 1995

Form approved.
Budget Bureau No. 1004-0136
Expires December 31, 1991

APPLICATION FOR PERMIT TO DRILL OR DEEPEN
DIVISION OF OIL, GAS & MINING

1a. TYPE OF WORK

DRILL ☒ DEEPEN ☐

b. TYPE OF WELL

OIL WELL ☐ GAS-WELL ☒ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐

2. NAME OF OPERATOR
CHEVRON USA PRODUCTION CO., INC.

3. ADDRESS AND TELEPHONE NO.
11002 EAST, 17500 SOUTH, VERNAL, UT 84078-8526 (801) 781-4300

4. LOCATION OF WELL. (Report location clearly and in accordance with any State requirements)*

At surface
1175' FSL, 1388' FWL, SESW

At proposed prod. zone
SAME

7. UNIT AGREEMENT NAME

RED WASH

8. FARM OR LEASE NAME, WELL NO.
#314

9. API WELL NO.

43-047-32626

10. FIELD AND POOL, OR WILDCAT
RED WASH
GREEN RIVER

11. SEC., T., R., M., OR BLOCK AND SURVEY
OR AREA
SEC. 29-T7S-R24E, SLB&M

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
31.8 MILES FROM VERNAL, UT

12. COUNTY OR PARISH
UINTAH

13. STATE
UTAH

15. DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any) 1175'

16. NO. OF ACRES IN LEASE
2560

17. NO. OF ACRES ASSIGNED
TO THIS WELL

NA

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT. 3493'

19. PROPOSED DEPTH
5327'

20. ROTARY OR CABLE TOOLS

ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5555' GL

22. APPROX. DATE WORK WILL START*
2/1/95

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55	24#	360'	190 SX.
7-7/8"	5-1/2" K-55	15.5#	5327'	611 SX.

We propose to drill for natural gas in the Green River Formation at the location specified. Enclosures:

- Certified Plat
- Self Certification Statement
- Thirteen Point Surface Use Plan With Attachments
- Eight Point Drilling Plan With Attachments

RECEIVED

DEC 22 1994

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Ed Conley TITLE TEAM LEADER DATE 12-19-94

(This space for Federal or State office use)

CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

PERMIT NO. NOTICE OF APPROVAL APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY Edwin J. Thomas TITLE ASSISTANT DISTRICT MANAGER MINERALS DATE FEB 23 1995

*See Instructions On Reverse Side

UT080-5M-092

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Chevron USA Production Co., Inc.

Well Name & Number: Red Wash 314

API Number: 43-047-32626

Lease Number: SL-071965

Location: SESW Sec. 29 T. 7S R. 24E

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The surface BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for a 2M system for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. A test plug will need to be used in testing the BOPE. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200' above the Uinta/Green River contact identified at $\pm 2392'$. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

4. Mud Program and Circulating Medium

As per Onshore Oil and Gas Order No. 2 sufficient quantities of mud materials will be maintained or readily accessible for the purpose of well control.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run at a minimum from the production casing shoe to $\pm 2192'$ and shall be utilized to determine the top of cement (TOC) and bond quality for production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours prior to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.), and shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Wayne Bankert (801) 789-4170
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

BLM FAX Machine (801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

CONDITIONS OF APPROVAL
SURFACE USE PLAN OF OPERATIONS



COAs Page 8 of 8
Well #RW314

A silt catchment dam and basin will be constructed according to BLM specifications approximately 1,200 ft. northeast of the location, where flagged. It will be located north of and downhill from the access road and will serve to reduce erosional impacts from the proposed access road.

The location is in crucial pronghorn habitat. Modification may be required to the Surface Use plan during the pronghorn kidding period May 15 to June 20.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.



NOTES

- Embankment slopes & dimensions shall be as shown on the Work Summary Chart
- Cut spillway to be constructed where no adequate natural spillway exists

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT DIVISION OF ENGINEERING SYSTEMS DENVER SERVICE CENTER	
TYPICAL MINOR RETENTION DAM	
DESIGNED <i>Ronald V. [Signature]</i>	
REVIEWED <i>[Signature]</i>	
APPROVED <i>[Signature]</i>	
DRAWN P.W. Twist J.D. Sedillo	SCALE NONE
DATE MARCH 9, 1984	SHEET OF
DRAWING NO. 02294-2	

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: CHEVRON USA

Well Name: RED WASH 314

Api No. 43-047-32626

Section 29 Township 7S Range 24E County UINTAH

Drilling Contractor

Rig #

SPUDDED: Date 4/9/95

Time

How DRY HOLE

Drilling will commence

Reported by KEVIN COPP

Telephone #

Date: 4/12/95 Signed: JLT

OPERATOR: Chevron USA Production Company
ADDRESS: 11002 East 17500 South
Vernal, Utah 84078-8526 (801)781-4300

OPERATOR ACCT. No. N0210

ENTITY ACTION FORM - FORM 6

Action Code	Current Entity No.	New Entity No.	API Number	Well Name	QQ	SC	TP	RG	County	Spud Date	Effective Date
B	99999	5678	43-047-32626	Red Wash Unit #314	SE%SW%	S29	T7S	R24E	Uintah	04/08/95	
WELL 1 COMMENTS: Well drilled as part of the Green River Participating Area within the Red Wash Unit <i>Entitles added 4-27-95. J</i>											
B	99999	5355	43-047-32459	Gypsum Hills Unit #11	NW%SE%	S20	T8S	R21E	Uintah	03/19/95	
WELL 2 COMMENTS: Well will be drilled as a unit well for production as part of the Gypsum Hills Secondary Recovery Unit											
B	99999	5355	43-047-32458	Gypsum Hills Unit #12	NE%SE%	S19	T8S	R21E	Uintah	03/10/95	
WELL 3 COMMENTS: Well will be drilled as a unit well for injection as part of the Gypsum Hills Secondary Recovery Unit											
B	99999	5355	43-047-32460	Gypsum Hills Unit #13	NE%SW%	S21	T8S	R21E	Uintah	04/10/95	
WELL 4 COMMENTS: Well will be drilled as a unit well for production as part of the Gypsum Hills Secondary Recovery Unit											
B	99999	5355	43-047-32647	Gypsum Hills Unit #14	NW%SW%	S20	T8S	R21E	Uintah	03/17/95	
WELL 5 COMMENTS: Well will be drilled as a unit well for production as part of the Gypsum Hills Secondary Recovery Unit											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected

(3/89)

RECEIVED

APR 27 1995

DIVISION OF
OIL, GAS & MINING

J. C. C. C.
Signature

Asset Team Leader 4-24-95
Title Date

Phone No. (801) 781-4300

OPERATOR: Chevron USA Production Company
ADDRESS: 11002 East 17500 South
Vernal, Utah 84078-8526 (801)781-4300

OPERATOR ACCT. No. N0210

ENTITY ACTION FORM - FORM 6

Action Code	Current Entity No.	New Entity No.	API Number	Well Name	QQ	SC	TP	RG	County	Spud Date	Effective Date
B	99999	5355	43-047-32648	Gypsum Hills Unit #15	SW%SW%	S20	T8S	R21E	Uintah	03/20/95	
WELL 1 COMMENTS: Well will be drilled as a unit well for production as part of the Gypsum Hills Secondary Recovery Unit <i>Entities added 4-27-95. Lee</i>											
B	99999	5355	43-047-32649	Gypsum Hills Unit #17	SW%SE%	S20	T8S	R21E	Uintah	04/13/95	
WELL 2 COMMENTS: Well will be drilled as a unit well for production as part of the Gypsum Hills Secondary Recovery Unit											
B	99999	5355	43-047-32650	Gypsum Hills Unit #18	SE%SE%	S20	T8S	R21E	Uintah	04/12/95	
WELL 3 COMMENTS: Well will be drilled as a unit well for production as part of the Gypsum Hills Secondary Recovery Unit											
B	99999	5265	43-047-32461	WVFU #119	NW%NW%	S21	T8S	R21E	Uintah	03/21/95	
WELL 4 COMMENTS: Well will be drilled as a unit well for production as part of the Wonsits Valley Federal Unit											
B	99999	5265	43-047-32462	WVFU #120	NE%NW%	S22	T8S	R21E	Uintah	03/23/95	
WELL 5 COMMENTS: Well will be drilled as a unit well for production as part of the Wonsits Valley Federal Unit											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected

(3/89)

RECEIVED

APR 27 1995

DIVISION OF
OIL, GAS & MINING

St. Paul
Signature
Asset Team Leader 4-24-95
Title Date
Phone No. (801) 781-4300

OPERATOR: Chevron USA Production Company
ADDRESS: 11002 East 17500 South
Vernal, Utah 84078-8526 (801)781-4300

OPERATOR ACCT. No. N0210

ENTITY ACTION FORM - FORM 6

Action Code	Current Entity No.	New Entity No.	API Number	Well Name	QQ	SC	TP	RG	County	Spud Date	Effective Date
B	99999	5670	43-047-32629	Red Wash Unit #306	NE%SW%	S23	T7S	R24E	Uintah	03/06/95	
WELL 1 COMMENTS: Well drilled as part of the Green River Participating Area within the Red Wash Unit											
B	99999	5670	43-047-32632	Red Wash Unit #307	SW%SW%	S16	T7S	R24E	Uintah	03/07/95	
WELL 2 COMMENTS: Well drilled as part of the Green River Participating Area within the Red Wash Unit											
B	99999	5670	43-047-32627	Red Wash Unit #308	SE%SW%	S28	T7S	R24E	Uintah	03/16/95	
WELL 3 COMMENTS: Well drilled as part of the Green River Participating Area within the Red Wash Unit											
B	99999	5670	43-047-32595	Red Wash Unit #312	SW%NE%	S34	T7S	R24E	Uintah	03/10/95	
WELL 4 COMMENTS: Well drilled as part of the Green River Participating Area within the Red Wash Unit											
B	99999	5670	43-047-32630	Red Wash Unit #313	NE%SW%	S20	T7S	R24E	Uintah	04/07/95	
WELL 5 COMMENTS: Well drilled as part of the Green River Participating Area within the Red Wash Unit											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected

(3/89)


RECEIVED

APR 27 1995

DIVISION OF
OIL, GAS & MINING

St. Crutcher
Signature
Asset Team Leader
Title
4-24-95
Date
Phone No. (801) 781-4300

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT



FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

USE "APPLICATION FOR PERMIT -" For such proposals.

6. Lease Designation and Serial No.

SL-071965

5. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

Red Wash

8. Well Name and No.

Red Wash #314

9. API Well No.

43-047-32626

10. Field and Pool, or Exploratory Area

Red Wash/Green River

11. County or Parish, State

Uintah Co., Utah

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

CHEVRON U.S.A. PRODUCTION CO.

3. Address and Telephone No.

P. O. BOX 4876

HOUSTON, TX 77210

ATTN: MARY COHLMIA

(713) 754-5068

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1175' FSL, 1388' FWL

SE SW Sec. 29-T7S, R24E, SLB&M

12 CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☐ Other

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-off

☐ Conversion to Injection

☐ Dispose Water

(Note: Report results of multiple completions on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work.

If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

THE PURPOSE OF THIS SUNDRY IS TO REPORT THE SPUD OF THE ABOVE WELL ON APRIL 8, 1995.

3-BLM VERNAL, 2-UTOGC, DRLG, RANGELY

14. I hereby certify that the foregoing is true and correct.

Signed: Mary Cohlmia

Title: DRILLING TECHNICAL ASSISTANT

Date: 4/25/95

(This space for Federal or State office use)

Approved by: _____

Title: _____

Date: _____

Conditions of approval, if any:

Title 18 U. S. C. Section 1001 makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

* See Instruction on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir
Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

Oil

Gas

☐

Well

☒

Well

☐

Other

2. Name of Operator

CHEVRON U.S.A. PRODUCTION COMPANY

3. Address and Telephone No.

11002 E. 17500 S. VERNAL, UT 84078-8526

Steve McPherson in Red Wash (801) 781-4310

or Gary Scott in Rangely, CO. (970) 675-3791

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1175' FSL & 1388' FWL (SE SW) SECTION 29, T7S, R24 E, SLBM

5. Lease Designation and Serial No.

SL-071965

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

RED WASH UNIT

8. Well Name and No.

RED WASH UNIT 314

9. API Well No.

43-047-32626

10. Field and Pool, or Exploratory Area

RED WASH - GREEN RIVER

11. County or Parish, State

UINTAH, UTAH

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒

Notice of Intent

☐

Subsequent Report

☐

Final Abandonment Notice

TYPE OF ACTION

☐

Abandonment

☐

Recompletion

☐

Plugging Back

☐

Casing Repair

☐

Altering Casing

☒

Other EXTENSION

☐

Change of Plans

☐

New Construction

☐

Non-Routine Fracturing

☐

Water Shut-Off

☐

Conversion to Injection

☐

Dispose Water

(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

CHEVRON IS REQUESTING A 1 YEAR EXTENSION ON OUR APPLICATION TO DRILL PERMIT WHICH WAS APPROVED 2/23/95.

A COPY OF THE APPROVED APPLICATION IS ATTACHED.

14. I hereby certify that the foregoing is true and correct.

Signed G.D. SCOTT

Title DRILLING TECHNICIAN

Date January 16, 1996

(This space for Federal or State office use)

Approved by:

Title


Date

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNIT STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Form approved
Budget Bureau No. 1004-01.16
Expires December 31, 1991



APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1. TYPE OF WORK

DRILL ☒ DEEPEN ☐

2. TYPE OF WELL

OIL
WELL ☐

GAS-
WELL ☒ OTHER ☐

SINGLE
ZONE ☐ MULTIPLE
ZONE ☐

3. LEASE AGREEMENT NAME

RED WASH

4. FARM OR LEASE NAME, WELL NO
#314

5. NAME OF OPERATOR

CHEVRON USA PRODUCTION CO., INC.

6. API WELL NO.

7. ADDRESS AND TELEPHONE NO.

11002 EAST, 17500 SOUTH, VERNAL, UT 84078-8526

(801) 781-4300

8. FIELD AND POOL, OR WILDCAT

RED WASH
GREEN RIVER

9. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*

At surface

1175' FSL, 1388' FWL, SESW

At proposed prod. zone

SAME

10. SEC., T., R., NL, OR BLOCK AND SURVEY

OR AREA
SEC. 29-T7S-R24E, SLB&M

11. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

31.8 MILES FROM VERNAL, UT

12. COUNTY OR PARISH

UTAH

13. STATE

UTAH

14. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any) 1175'

15. NO. OF ACRES IN LEASE

2560

16. NO. OF ACRES ASSIGNED
TO THIS WELL

NA

17. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT. 3493'

18. PROPOSED DEPTH

5327'

19. ROTARY OR CABLE TOOLS

ROTARY

20. ELEVATIONS (Show whether OF, RT, GR, etc.)

5555' GL

21. APPROX. DATE WORK WILL START*

2/1/95

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55	24#	360'	190 SX.
7-7/8"	5-1/2" K-55	15.5#	5327'	611 SX.

We propose to drill for natural gas in the Green River Formation at the location specified. Enclosures:

- Certified Plat
- Self Certification Statement
- Thirteen Point Surface Use Plan With Attachments
- Eight Point Drilling Plan With Attachments

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

22. SIGNED Lo Bouley TITLE TEAM LEADER DATE 12-19-94

(This space for Federal or State office use)

PERMIT NO. 43-047-32626

APPROVAL DATE

2/22/95

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

TITLE

DATE

DATE

*See Instructions On Reverse Side

WELL SPACING:

(June 1990)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir

Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

Oil

Gas

☐

Well

☒

Well

☐

Other

2. Name of Operator

CHEVRON U.S.A. PRODUCTION COMPANY

3. Address and Telephone No

11002 E. 17500 S. VERNAL, UT 84078-8526

(801) 781-4300

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1175' FSL & 1388' FWL (SE SW) SECTION 29, T7S, R24E, SLBM

5. Lease Designation and Serial No.

SL-071965

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

RED WASH UNIT

8. Well Name and No.

RED WASH UNIT 314

9. API Well No.

43-047-32626

10. Field and Pool, or Exploratory Area

RED WASH - GREEN RIVER

11. County or Parish, State

UINTAH, UTAH

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒

Notice of Intent

☐

Subsequent Report

☐

Final Abandonment Notice

TYPE OF ACTION

☐

Abandonment

☐

Recompletion

☐

Plugging Back

☐

Casing Repair

☐

Altering Casing

☒

Other TA STATUS OF WELL

☐

Change of Plans

☐

New Construction

☐

Non-Routine Fracturing

☐

Water Shut-Off

☐

Conversion to Injection


☐

Dispose Water

(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

CHEVRON IS REQUESTING A TA STATUS ON THE ABOVE WELL. WE WILL EVALUATE THIS WELL FOR DRILL AND COMPLETE OR P&A DURING 1998.



14. I hereby certify that the foregoing is true and correct.

Signed

J C Janner

Title

COMPUTER SYSTEMS OPERATOR

Date

12/9/97

(This space for Federal or State office use)

Approved by:

Title

Date

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir
Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

Oil

Gas

☐

Well

☒

Well

☐

Other

2. Name of Operator

CHEVRON U.S.A. PRODUCTION COMPANY

3. Address and Telephone No

11002 E. 17500 S. VERNAL, UT 84078-8526

(801) 781-4306

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1175' FSL & 1388' FWL (SE SW) SECTION 29, T7S, R24E, SLBM

5. Lease Designation and Serial No.

SL-071965

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

RED WASH UNIT

8. Well Name and No.

RED WASH UNIT 314

9. API Well No.

43-047-32626

10. Field and Pool, or Exploratory Area

RED WASH - GREEN RIVER

11. County or Parish, State

UINTAH, UTAH

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒

Notice of Intent

☐

Subsequent Report

☐

Final Abandonment Notice

TYPE OF ACTION

☒

Abandonment

☐

Recompletion

☐

Plugging Back

☐

Casing Repair

☐

Altering Casing

☐

Other _____

☐

Change of Plans

☐

New Construction

☐

Non-Routine Fracturing

☐

Water Shut-Off

☐

Conversion to Injection


☐

Dispose Water

(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

WE INTEND TO PLUG AND ABANDON THIS WELL PER THE ATTACHED.



14. I hereby certify that the foregoing is true and correct.

Signed

D. C. BEAMAN

D C Beaman

Title

COMPUTER SYSTEMS OPERATOR

Date

3/3/1999

(This space for Federal or State office use)

Approved by:

Title

Date

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**RED WASH UNIT #314
1175' FSL & 1388' FWL
NESW-SEC.29-T7S-R24E
UINTAH COUNTY, UTAH**

API#: 43-047-32626
LEASE NUMBER: SL-071965

KB ELEVATION: NA
GL ELEVATION: 5555'
TD: 376'
PBSD: NA

CASING DETAIL:

12-1/4" HOLE SIZE
8-5/8" 24# K-55 @ 375' W/200 SX. CLASS G CEMENT TO SURFACE

COMMENTS:

The gas well originally planned to be drilled at this location was cancelled after surface casing was set. There are no plans for future drilling.

PLUGGING PROCEDURE:

1. BAIL FLUID LEVEL TO ~50.
2. MIX NEAT CEMENT AND FILL TO SURFACE.
3. INSTALL LOCATION MARKER OR SUBSURFACE PLATE AS DIRECTED BY REGULATORY AGENCIES.
4. TURN OVER TO OPERATIONS FOR LOCATION REHABILITATION.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir
Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well	
Oil	Gas
<input type="checkbox"/> Well	<input checked="" type="checkbox"/> Well <input type="checkbox"/> Other
2. Name of Operator	CHEVRON U.S.A. PRODUCTION COMPANY
3. Address and Telephone No	11002 E. 17500 S. VERNAL, UT 84078-8526 (801) 781-4306
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)	1175' FSL & 1388' FWL (SE SW) SECTION 29, T7S, R24E, SLBM

5. Lease Designation and Serial No.	SL-071965
6. If Indian, Allottee or Tribe Name	N/A
7. If Unit or CA, Agreement Designation	RED WASH UNIT
8. Well Name and No.	RED WASH UNIT 314
9. API Well No.	43-047-32626
10. Field and Pool, or Exploratory Area	RED WASH - GREEN RIVER
11. County or Parish, State	UINTAH, UTAH

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input checked="" type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Other _____	<input type="checkbox"/> Dispose Water


(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

THIS WELL WAS PLUGGED AND ABANDONED ON 3/9/99 AS FOLLOWS:

1. CEMENT 50' TO SURFACE WITH REDY MIX TRUCK
2. INSTALL DRY HOLE PLATE

Witnessed by Ed Forsman with BLM



14. I hereby certify that the foregoing is true and correct.
Signed D. C. BEAMAN DC Beaman Title COMPUTER SYSTEMS OPERATOR Date 3/15/1999

(This space for Federal or State office use)

Approved by: _____ Title _____ Date _____
Conditions of approval, if any _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir

Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

Oil

Gas

☐

Well

☒

Well

☐

Other

2. Name of Operator

CHEVRON U.S.A. PRODUCTION COMPANY

3. Address and Telephone No

11002 E. 17500 S. VERNAL, UT 84078-8526

(801) 781-4306

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1175' FSL & 1388' FWL (SE SW) SECTION 29, T7S, R24E, SLBM

5. Lease Designation and Serial No.

SL-071965

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

RED WASH UNIT

8. Well Name and No.

RED WASH UNIT 314

9. API Well No.

43-047-32626

10. Field and Pool, or Exploratory Area

RED WASH - GREEN RIVER

11. County or Parish, State

UINTAH, UTAH

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒

Notice of Intent

☐

Subsequent Report

☐

Final Abandonment Notice

TYPE OF ACTION

☐

Abandonment

☐

Recompletion

☐

Plugging Back

☐

Casing Repair

☐

Altering Casing

☒

Other **CLEAR SURFACE**

☐

Change of Plans

☐

New Construction

☐

Non-Routine Fracturing

☐

Water Shut-Off

☐

Conversion to Injection

☐


Dispose Water

(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

After PA of well.

We request permission to abandon and reclaim all surface facilities and equipment including pits and surface pipelines. We also request permission to bury all cement pumping unit pads and well cellars. After cleanup, locations and right of ways will be seeded per BLM specifications.



14. I hereby certify that the foregoing is true and correct.

Signed **D. C. BEAMAN**

D C Beaman

Title **COMPUTER SYSTEMS OPERATOR**

Date **3/18/1999**

(This space for Federal or State office use)

Approved by:

Title

Date

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE
(See other instructions on
reverse side).

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

<p>1a. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> Other <u>SURFACE CASING</u></p> <p>b. TYPE OF COMPLETION</p> <p>NEW WELL <input type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR <input type="checkbox"/> Other <u>N/A</u></p>		<p>5. LEASE DESIGNATION AND SERIAL NO. SL-071965</p> <p>6. IF INDIAN, ALLOTTEE OR TRIBE NAME</p> <p>7. UNIT AGREEMENT NAME RED WASH UNIT</p> <p>8. FARM OR LEASE NAME</p> <p>9. WELL NO. RWU #314</p> <p>10. FIELD AND POOL, OR WILDCAT RED WASH - GREEN RIVER</p> <p>11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA SEC. 29-T7S-R24E, SLBM</p>																																			
<p>2. NAME OF OPERATOR CHEVRON USA PRODUCTION CO., INC.</p> <p>3. ADDRESS OF OPERATOR 11002 EAST 17500 SOUTH, VERNAL, UT 84078-8526</p> <p>4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface 1175' FSL, 1388' FWL, NESW At top rod. interval reported below SAME At total depth</p>		<div style="border: 2px solid black; padding: 10px; width: fit-content; margin: 0 auto;"><p style="font-size: 2em; margin: 0;">RECEIVED</p><p style="font-size: 1.5em; margin: 0;">APR 2 1999</p><p style="font-size: 1.2em; margin: 0;">DIV. OF OIL, GAS & MINING</p></div>																																			
<p>14. PERMIT NO. 43-047-32626</p>		<p>DATE ISSUED 2/23/95</p>		<p>12. COUNTY OR PARISH UINTAH</p>		<p>13. STATE UT</p>																															
<p>15. DATE SPUDDED 4/8/95</p>		<p>16. DATE T.D. REACHED 4/8/95</p>		<p>17. DATE COMPL. (Ready to prod.) N/A 3/9/99</p>		<p>18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 5555' GL</p>		<p>19. ELEV. CASINGHEAD N/A</p>																													
<p>20. TOTAL DEPTH, MD & TVD 375'</p>		<p>21. PLUG BACK T.D., MD & TVD N/A</p>		<p>22. IF MULTIPLE COMPL., HOW MANY* N/A</p>		<p>23. INTERVALS DRILLED BY ROTARY TOOLS X</p>		<p>CABLE TOOLS</p>																													
<p>24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)* N/A</p>								<p>25. WAS DIRECTIONAL SURVEY MADE N/A</p>																													
<p>26. TYPE ELECTRIC AND OTHER LOGS RUN</p>								<p>27. WAS WELL CORED</p>																													
<p>28. CASING RECORD (Report all strings set in well)</p>																																					
CASING SIZE		WEIGHT, LB./FT.		DEPTH SET (MD)		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED																											
8-5/8"		24		375'		12-1/4"		200 SX. CLASS G		N/A																											
<p>29. LINER RECORD</p>										<p>30. TUBING RECORD</p>																											
SIZE		TOP (MD)		BOTTOM (MD)		SACKS CEMENT*		SCREEN (MD)		SIZE		DEPTH SET (MD)		PACKER SET (MD)																							
<p>31. PERFORATION RECORD (Interval, size and number) THIS WELL WAS SUSPENDED AFTER SETTING SURFACE CASING. THE SURFACE CASING HAS BEEN PLUGGED.</p>										<p>32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC. DEPTH INTERVAL (MD) AMOUNT AND KIND OF MATERIAL USED</p>																											
<p>33. * PRODUCTION</p> <table border="1" style="width:100%; border-collapse: collapse;"><tr><td colspan="2">DATE FIRST PRODUCTION</td><td colspan="6">PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump)</td><td colspan="2">WELL STATUS (Producing or shut-in) PA</td></tr><tr><td>DATE OF TEST</td><td>HOURS TESTED</td><td>CHOKE SIZE</td><td>PROD'N FOR TEST PERIOD</td><td>OIL--BBL.</td><td>GAS--MCF.</td><td>WATER--BBL.</td><td>GAS-OIL RATIO</td></tr><tr><td>FLOW. TUBING PRESS.</td><td>CASING PRESSURE</td><td>CALCULATED 24-HOUR RATE</td><td>OIL--BBL.</td><td>GAS--MCF.</td><td>WATER--BBL.</td><td colspan="2">OIL GRAVITY-API (CORR.)</td></tr></table>										DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump)						WELL STATUS (Producing or shut-in) PA		DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL--BBL.	GAS--MCF.	WATER--BBL.	GAS-OIL RATIO	FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL--BBL.	GAS--MCF.	WATER--BBL.	OIL GRAVITY-API (CORR.)			
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump)						WELL STATUS (Producing or shut-in) PA																													
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL--BBL.	GAS--MCF.	WATER--BBL.	GAS-OIL RATIO																														
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL--BBL.	GAS--MCF.	WATER--BBL.	OIL GRAVITY-API (CORR.)																															
<p>34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)</p>										<p>TEST WITNESSED BY</p>																											
<p>35. LIST OF ATTACHMENTS</p>																																					
<p>36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records</p> <table border="0" style="width:100%;"><tr><td style="width:30%;">SIGNED <u><i>Chris C. Brown</i></u></td><td style="width:30%;">TITLE <u><i>Computer Systems Operator</i></u></td><td style="width:40%;">DATE <u><i>3/31/99</i></u></td></tr></table>												SIGNED <u><i>Chris C. Brown</i></u>	TITLE <u><i>Computer Systems Operator</i></u>	DATE <u><i>3/31/99</i></u>																							
SIGNED <u><i>Chris C. Brown</i></u>	TITLE <u><i>Computer Systems Operator</i></u>	DATE <u><i>3/31/99</i></u>																																			

(See Instructions and Spaces for Additional Data on Reverse Side)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir
Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

Oil Gas
☐ Well ☐ Well ☒ Other MULTIPLE WELLS SEE ATTACHED LIST

2. Name of Operator

CHEVRON U.S.A. INC.

3. Address and Telephone No

11002 E. 17500 S. VERNAL, UT 84078-8526

(801) 781-4300

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

5. Lease Designation and Serial No.

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

RED WASH UNIT
I-SEC NO 761

8. Well Name and No.

9. API Well No.

10. Field and Pool, or Exploratory Area

RED WASH - GREEN RIVER

11. County or Parish, State

UINTAH, UTAH

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other CHANGE OF OPERATOR
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

As of January 1, 2000 Chevron U.S.A. INC. resigns as Operator of the Red Wash Unit.
The Unit Number is I-SEC NO 761 effective October 31, 1950.

The successor operator under the Unit Agreement will be
Shenandoah Energy Inc.
475 17th Street, Suite 1000
Denver, CO 80202

Agreed and accepted to this 29th day of December, 1999

Shenandoah Energy Inc.

By: Mitchell L. Solich
President

RECEIVED

DEC 30 1999

DIVISION OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.

Signed A. E. Wacker

Title Assistant Secretary

Date 12/29/99

(This space for Federal or State office use)

Approved by:

Title

Date

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

FEB 07 2000

DIVISION OF
OIL, GAS AND MINING

IN REPLY REFER TO
UT-931

February 4, 2000

Shenandoah Energy Inc.
Attn: Rae Cusimano
475 17th Street, Suite 1000
Denver, Colorado 80202

Re: Red Wash Unit
Uintah County, Utah

Gentlemen:

On December 30, 1999, we received an indenture whereby Chevron U.S.A. Inc. resigned as Unit Operator and Shenandoah Energy Inc. was designated as Successor Unit Operator for the Red Wash Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 4, 2000. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Red Wash Unit Agreement.

Your statewide (Utah) oil and gas bond No. 0969 will be used to cover all operations within the Red Wash Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

cc: Chevron U.S.A. Inc.

bcc: Field Manager - Vernal (w/enclosure)

Minerals Adjudication Group U-932
File - Red Wash Unit (w/enclosure)
MMS - Data Management Division
Agr. Sec. Chron
Fluid Chron

UT931:TAThompson:tt:2/4/00

Well Status Report
Utah State Office
Bureau of Land Management

Lease	Api Number	Well Name	QTR	Section	Township	Range	Well Status	Operator
UTU0559	4304731581	293 (22-22A) RED WAS SENW	22	T	7S	R22E	OSI	CHEVRON U S A INCORPORATED
UTU02148	4304731582	294 (24-18C) RED WAS SESW	18	T	7S	R24E	PGW	CHEVRON U S A INCORPORATED
UTU081	4304731577	295 (11-22B) RED WAS NWNW	22	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU0566	4304731578	296 (12-35B) RED WAS SWNW	35	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU081	4304731579	297 (24-15B) RED WAS SESW	15	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU0566	4304731679	298 (22-27B) RED WAS SENW	27	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU0116	4304733018	299 SWNE	18	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU082	4304715136	3 (34-23B) RED WASH SWSE	23	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU081	4304715157	30 (23-13B) RED WASH NESW	13	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU081	4304731682	301 (43-15B) RED WAS NESE	15	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU082	4304731683	302 (22-24B) RED WAS SENW	24	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU0116	4304731819	303 (34-17B) RED WAS SWSE	17	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU0830	4304732538	305 NENE	4	T	8S	R24E	PGW	CHEVRON U S A INCORPORATED
UTU093	4304732629	306 NESW	23	T	7S	R24E	POW	CHEVRON U S A INCORPORATED
STATE	4304732632	307 SWSW	16	T	7S	R24E	ABD	CHEVRON U S A INCORPORATED
UTSL071965	4304732627	308 SESW	28	T	7S	R24E	P+A	CHEVRON U S A INCORPORATED
UTU081	4304715158	31 (34-22B) RED WASH SWSE	22	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTSL071965	4304732628	311 NESW	26	T	7S	R24E	P+A	CHEVRON U S A INCORPORATED
UTSL071963	4304732595	312 SWNE	34	T	7S	R24E	ABD	CHEVRON U S A INCORPORATED
UTU02149	4304732630	313 NESW	20	T	7S	R24E	ABD	CHEVRON U S A INCORPORATED
UTSL071965	4304732626	314 SESW	29	T	7S	R24E	ABD	CHEVRON U S A INCORPORATED
UTU081	4304715160	33 (14-14B) RED WASH SWSW	14	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU081	4304715161	34 (23-14B) RED WASH NESW	14	T	7S	R23E	WIW	CHEVRON U S A INCORPORATED
UTU081	4304715162	35 (43-13B) RED WASH NESE	13	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU081	4304715163	36 (32-13B) RED WASH SWNE	13	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU0823	4304715164	37 (41-25B) RED WASH NENE	25	T	7S	R23E	ABD	CHEVRON U S A INCORPORATED
UTU082	4304715165	38 (14-23B) RED WASH SWSW	23	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU0561	4304715166	39 (14-24A) RED WASH SWSW	24	T	7S	R22E	TA	CHEVRON U S A INCORPORATED
UTU081	4304715137	4 (41-22B) RED WASH NENE	22	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU082	4304715167	40 (21-24B) RED WASH NENW	24	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU081	4304715168	41 (34-13B) RED WASH SWSE	13	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTSL071965	4304715169	42 (21-29C) RED WASH NENW	29	T	7S	R24E	PGW	CHEVRON U S A INCORPORATED
UTU0116	4304715170	43 (12-17B) RED WASH SWNW	17	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU0829	4304715171	44 (32-33C) RED WASH SWNE	33	T	7S	R24E	PGW	CHEVRON U S A INCORPORATED
UTU02030	4304715172	45 (23-30B) RED WASH NESW	30	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU080	4304715173	46 (41-21C) RED WASH NENE	21	T	7S	R24E	PGW	CHEVRON U S A INCORPORATED
UTU02030	4304715174	48 (32-19B) RED WASH SWNE	19	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU02025	4304715175	49 (12-29B) RED WASH SWNW	29	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU082	4304715138	5 (41-23B) RED WASH NENE	23	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU0559	4304715176	50 (14-23A) RED WASH SWSW	23	T	7S	R22E	POW	CHEVRON U S A INCORPORATED
STATE	4304715177	51 (12-16B) RED WASH SWNW	16	T	7S	R23E	POW	CHEVRON U S A INCORPORATED
UTU0116	4304715178	52 (14-18B) RED WASH SWSW	18	T	7S	R23E	TA	CHEVRON U S A INCORPORATED
UTU0561	4304715179	53 (41-25A) RED WASH NENE	25	T	7S	R22E	POW	CHEVRON U S A INCORPORATED
UTU0559	4304715181	55 (41-21A) RED WASH NENE	21	T	7S	R22E	P+A	CHEVRON U S A INCORPORATED
UTU02030	4304715182	56 (41-28B) RED WASH NENE	28	T	7S	R23E	WIW	CHEVRON U S A INCORPORATED
UTU02148	4304715183	57 (12-18C) RED WASH SWNW	18	T	7S	R24E	POW	CHEVRON U S A INCORPORATED
UTU082	4304716477	59 (12-24B) RED WASH SWNW	24	T	7S	R23E	WIW	CHEVRON U S A INCORPORATED
UTU0567	4304716482	6 (41-21B) RED WASH NENE	21	T	7S	R23E	WIW	CHEVRON U S A INCORPORATED
UTU02025	4304715184	60 (43-30B) RED WASH NESE	30	T	7S	R23E	TA	CHEVRON U S A INCORPORATED

3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 08-23-2000
4. Is the new operator registered in the State of Utah: YES Business Number: 224885
5. If **NO**, the operator was contacted on: _____
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 02/04/2000
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 02/04/2000
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: N/A
9. **Underground Injection Control ("UIC") Pro:** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 09/25/2000
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 09/25/2000
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: 159261960

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed has furnished a bond: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

FILMING:

1. All attachments to this form have been **MICROFILMED** on: 03-09-01

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: _____

COMMENTS:

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH		4-KAS
2. CDW		5- <i>SP</i>
3. JLT		6-FILE

Enter date after each listed item is completed

X Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

Merger

The operator of the well(s) listed below has changed, effective:

01-01-2000**FROM:** (Old Operator):

CHEVRON USA INC

Address: 11002 E. 17500 S.

VERNAL, UT 84078-8526

Phone: 1-(435)-781-4300

Account No. N0210

TO: (New Operator):

SHENANDOAH ENERGY INC

Address: 11002 E. 17500 S.

VERNAL, UT 84078

Phone: 1-(435)-781-4300

Account N4235

CA No.

Unit: RED WASH

WELL(S)

NAME	API NO.	ENTITY NO.	SEC. TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
RWU 39 (14-24A)	43-047-15166	5670	24-07S-22E	FEDERAL	OW	TA
RWU 35 (43-13B)	43-047-15162	5670	13-07S-23E	FEDERAL	OW	TA
RWU 36 (32-13B)	43-047-15163	5670	13-07S-23E	FEDERAL	GW	P
RWU 41 (34-13B)	43-047-15168	5670	13-07S-23E	FEDERAL	OW	P
RWU 33 (14-14B)	43-047-15160	5670	14-07S-23E	FEDERAL	GW	S
RWU 51 (12-16B)	43-047-15177	5670	16-07S-23E	STATE	OW	P
RWU 43 (12-17B)	43-047-15170	5670	17-07S-23E	FEDERAL	OW	P
RWU 52 (14-18B)	43-047-15178	5670	18-07S-23E	FEDERAL	OW	TA
RWU 4 (41-22B)	43-047-15137	5670	22-07S-23E	FEDERAL	OW	TA
RWU 38 (14-23B)	43-047-15165	5670	23-07S-23E	FEDERAL	OW	P
RWU 5 (41-23B)	43-047-15138	5670	23-07S-23E	FEDERAL	OW	P
RWU 50 (14-23A)	43-047-15176	5670	23-07S-22E	FEDERAL	OW	P
RWU 40 (21-24B)	43-047-15167	5670	24-07S-23E	FEDERAL	OW	TA
RWU 37 (41-25B)	43-047-15164	5670	25-07S-23E	FEDERAL	GW	PA
RWU 49 (12-29B)	43-047-15175	5670	29-07S-23E	FEDERAL	OW	TA
RWU 313	43-047-32630	5670	20-07S-24E	FEDERAL	GW	PA
RWU 46 (41-21C)	43-047-15173	5670	21-07S-24E	FEDERAL	GW	P
RWU 311	43-047-32628	5670	26-07S-24E	FEDERAL	OW	PA
RWU 314	43-047-32626	5670	29-07S-24E	FEDERAL	GW	PA
RWU 42 (21-29C)	43-047-15169	5670	29-07S-24E	FEDERAL	GW	P
RWU 44 (32-33C)	43-047-15171	5670	33-07S-24E	FEDERAL	GW	P
RWU 312	43-047-32595	5670	34-07S-24E	FEDERAL	GW	PA

OPERATOR CHANGES DOCUMENTATION1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on:12-30-19992. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on:08-09-2000